

# Concrete Works LLC

P.O. Box 2204  
Buford, GA. 30515  
T 678 758-9925  
F 678 482-2068  
val@concreteworksllc.com

# Proposal

Date	Estimate #
5/22/2013	718

Name / Address

Project

Qty	Description	Rate	Total
	FOUNDATION WALL		
27.5	LF 10" x 3' Wall Front of house with ledge to catch front porch	41.00	1,127.50
72	LF 8" x 3' Wall	39.00	2,808.00
67.5	LF 8" x 4' Wall ( one foot stepdown middle of house )	45.00	3,037.50
9	3' tall column	95.00	855.00
90	Anchor Bolts	3.00	270.00
2	VF footing jumps	25.00	50.00
0.9	Tons rebar supply	1,500.00	1,350.00
0.9	rebar tied	750.00	675.00
	ESTIMATE ONLY. Final price will be based with measurements at the field		
	NOTE: Pumps are NOT included at this time. Rock lot or soft soil will cost extra labor and/or concrete Price includes labor and materials Line pump mix add \$14.00 per yard ALL footings to be 2' wide by 12" deep, with 2 runs of #4 rebar. Walls with rebar tied 16" o/c		

We look forward to working with you

**Total**

\$10,173.00

Accepted by:

Date:

Title: